



Wetlands NOI Project Information

Related links

There are no related links for displayed element.

NOI Number ?
105-0989

Applicant Information
BELLINGHAM DPW

Filing Date ?
07/03/2025

Filing Type ?
NOI

Project Type
Utilities,
I-LP: Public utilities

Project Address
WRENTHAM ROAD

Comments
THE PROPOSED PROJECT CONSISTS OF THE CONSTRUCTION OF THREE REPLACEMENT WELLS AND ASSOCIATED PROLONGED PUMP TESTS, THE DECOMMISSIONING OF THREE EXISTING WELLS, THE REPLACEMENT OF PUMPING EQUIPMENT IN ONE EXISTING WELL, THE INSTALLATION OF NEW UNDERGROUND UTILITIES AND RAW WATER MAINS, THE CONSTRUCTION OF FOUR METERING PITS, THE INSTALLATION OF ONE HYDRANT, THE INSTALLATION OF A PROPANE TANK AND GENERATOR ON CONCRETE PADS, REPAVING AND APPURTENANCES. THE EXISTING RAW WATER MAINS WILL BE EITHER CAPPED AND ABANDONED IN PLACE OR REMOVED AT THE CONTRACTOR'S DISCRETION.

Technical Comments
Per 310 CMR 10.53(3)(o)d., compensatory storage shall be provided for all flood storage volume that will be lost in accordance with procedures outlined in 310 CMR 10.57(4)(a)1. The Applicant should submit additional information demonstrating how the proposed flood storage loss (800 cf) will not cause an increase or contribute incrementally to an increase in the horizontal extent and level of flood waters during peak flows.

Inland Resource Areas

RESOURCE AREA ALTERED	PROPOSED ALTERATION	PROPOSED REPLACEMENT
BORDERING LAND SUBJECT TO FLOODING	9920 (square feet) 800 (Cubic feet)	9520 (square feet) 800 (Cubic feet)

Coastal Resource Areas

RESOURCE AREA ALTERED	PROPOSED ALTERATION	PROPOSED REPLACEMENT
-----------------------	---------------------	----------------------

◀ PREVIOUS

Q SEARCH AGAIN